



mixertrucks.com
CHAPARRAL
CONCRETE EQUIPMENT

MAIN OFFICE
1701 W. Northwest Hwy
Grapevine TX, 76051

Tel: 817-329-9935
Fax: 817-329-9936
1-888-886-4937



1990 McNeilus 10yd
(200 YD³/HR)

AGG BIN 50T IN 2 COMPARTMENT
AGG BATCHER 10 YARD CPMB RATED
GRAVITY CEMENT SILO 50T
CEMENT BATCHER 4 LOAD CELLS
DIGITAL READ-OUT, AIR
VIBRATOR AERATION PADS
10 YD CPMB RATED
BATCH TRANSFER BELT 28" WIDE, 300
FPM, 4" 35°, CEMA B IDLERS
TWO PLY BELT 10 HP,
BACKSTOP

AIR SYSTEM 10HP COMPRESSOR
ELECTRICAL SYSTEM

440 V POWER PANEL WITH
STARTERS FOR BATCH BELT
AND AIR COMPRESSOR

CONTROL SYSTEM

ELECTRONIC MANUAL
PANEL WITH DRO'S FOR
CEMENT AND AGGREGATES

File: SS_MTM10YD_HOU_TX



mixertrucks.com
CHAPARRAL
CONCRETE EQUIPMENT

MAIN OFFICE
1701 W. Northwest Hwy
Grapevine TX, 76051

Tel: 817-329-9935
Fax: 817-329-9936
1-888-886-4937

