



mixertrucks.com
CHAPARRAL
CONCRETE EQUIPMENT

MAIN OFFICE
1701 W. Northwest Hwy
Grapevine TX, 76051

Tel: 817-329-9935
Fax: 817-329-9936
1-888-886-4937



SoLo 5LP (100 YD³/HR)

AGG BIN 25T IN 2 EQUAL, INLINE
AGG BATCHER 5 YARD CPMB RATED
GRAVITY CEMENT SILO 150 BBL CPMB
RATED (20 Tons)
SCREW CONVEYOR 6", 7.5 HP SCREW
CONVEYOR
CEMENT BATCHER 4 LOAD CELLS
DIGITAL READ-OUT, AIR
VIBRATOR AERATION PADS
5 YD CPMB RATED, 10"
DISCHARGE VALVE.
BATCH TRANSFER BELT 24" WIDE, 300
FPM, 4" 35°, CEMA B IDLERS
TWO PLY BELT 10 HP,
BACKSTOP
WATER SYSTEM 2", 160 GPM, 60
PSI BADGER HOT WATER
METER W/ELECTRIC CUT
OFF VALVE

AIR SYSTEM 5HP, 80 GAL TANK

ELECTRICAL SYSTEM
440 V POWER PANEL WITH
STARTERS FOR BATCH BELT
AND AIR COMPRESSOR

CONTROL SYSTEM
ELECTRONIC MANUAL
PANEL WITH DRO'S FOR
CEMENT AND AGGREGATES

File: SPECS SoLo 5LP